



Gas will be delivered to the LNG facility via buried gas transmission pipeline. The construction of the pipeline will have to comply with the Australian Standard AS2885 - Gas and Liquid Petroleum.

The construction of the pipeline is anticipated to take approximately 18 months and will follow a typical construction sequence.

Construction Sequence

- Construction preparation works;
- Right of Way (ROW) establishment;
- Clearing of vegetation along an approved construction corridor;
- The delivery of pipe to laydown areas;
- Pipeline trenching;
- Pipeline assembly, (welding) and lowering into the trench;
- Backfill and pipeline burial;
- Reinstatement and rehabilitation of the land; and
- Testing and commissioning of the pipeline.